

01 66 00 – Product Storage and Handling Requirements

1. General

- A. Materials and Equipment cannot be stored on sidewalks, loading docks, green spaces, forests or landscaped areas. Materials must be delivered to and stored in the Owner-approved staging area. All other storage of materials is subject to written preapproval by the Owner.

2. Contractor Staging

- A. Vehicles belonging to employees of the Contractor may not be parked anywhere on campus unless a suitable parking location has been specifically identified in the logistics plan and approved by the Owner. Parking on paved streets, sidewalks, landscaped or grass areas, or forests is prohibited
- B. All material storage and staging will be within the project area as shown in the drawings. All materials stored within the project site shall be the responsibility of the Contractor.