

## 03 40 00 – Precast Concrete

### 1. General

- A. Precast architectural panels using Duke stone as an aggregate shall be in accordance with specifications covering Duke stone elsewhere in these guidelines. Design of precast concrete panels with exposed aggregate shall be approved by the Consultant and Owner through the use of finish samples or mock-ups. Colors and textures shall be in context with existing architectural elements on campus. Precast concrete materials shall be produced by a manufacturer who is thoroughly experienced in their production. Sealing compounds, matrix design, finish and joint sealers shall be considered in the long-term maintenance of precast concrete systems.